



Indian Institute of Information Technology, Sri City, Chittoor

No. IIITS/NIT/WORK/CABINS/2021/08,

dt 15.03.2021

CORRIGENDUM FOR REVISED BOQ

Sub.: Corrigendum for Revised BoQ

Ref.: Tender Ref.No. IIITS/NIT/WORK/CABINS/2021/08, dated 15.03.2021

The bid has been invited vide above mentioned tender for Interior works- Providing New Faculty Cabins in 2nd floor of Academic Block, at IIIT Sri City, in which One item has been added in BoQ and quantities for 4 items have been increased .

Interested bidders must quote their price in the revised BOQ.

Date is extended till 12 July 2021, 03:00 PM

Any other modification/corrigendum in future shall be published on IIIT Sri City website www.iiits.ac.in

All other Terms and Conditions of the Tender Document will remain the same.

Registrar I/c.

Constructing New Faculty's Cabins in Second Floor Academic Block (NW)

S No	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	FULL HEIGHT WALL PARTITION				
	Providing and fixing Full ht. double skin Partitions as per specifications including skirting, complete as per the drawings and instructions complete in all respects.	SQM	74		
	Main frame -2"x2" Aluminium section of 16 Gauge verticals at minimum 1' 6"-2'-0" Centre spacing approx and 2" X 1" size Aluminium sections horizontal at 1' 6"-2'-0" Centre spacing approx extra frame below slab soffit for conduit to run above. All verticals secured to ceiling.				
	Skin:- Both side with 12mm thk Gypsum Board screwed to frame work on both sides with joints as per manufacturer specifications with smooth finish				
	Insulation:- Shall be 50mm thick Rock Wool insulation fixed properly of 12kg/Sqm density.				
	SKIRTING : In the same alignment, 4" high in 12mm thk Gyp Board with a groove finished with laminate / veneer as directed by Engineer-In-Charge.				
	MAKE: AEROLITE / GYPROC / CREDESCENCE / HILUX OR EQUIVALENT				
2	GLASS WALL PARTITION				
	Providing and fixing frameless glass partition with 12mm toughened glass frosted/etched with necessary patch fittings of approved make as shown in the drawing and as per the directions of Engineer-In-Charge.	SQM	36.19		
	MAKE: SAINT GOBAIN / DORMA / HAFFLE / HETTICH / DORSET OR EQUIVALENT				
3	Door Frames				
	Providing and fixing in position Anodised /Poweder coated Aluminium box frame of size 63x38x3 mmthick from JINDAL profile number 20004 from double groove of 1.790 kg per runningmeter or 20005 from Single groove of 1.777 kg per runningmeter. , shaped, planed and fixed with necessary jointing method approved including pins, nails, screws and bolts etc. Rate shall include for cost of bolts, nuts, screws, nails, pins, approved hold fast and grouting for fixing anchor fasteners / coach screws and including t of approved colour etc. complete, as directed. . shall be approved by PMC as per design calcutionaand shop drawing of Frames and accesories.				
	D2 frames second floor 1500x2600 (B)	Kgs	13		
4	Door Shutters				

	Providing and fixing thick flush door shutters (Jacson or approved equivalent make) single leaf of any size of solid core of block board type bonded with phenol formaldehyde synthetic resin thermo pressed with 8 mm thick teak wood external lipping. The construction procedure of the shutter should be as per IS 2202. The shutter shall be shop prepared for taking mortice lock or latches suitable lock block of wood may be provided for fixing the hardware. The size of block, shall perfectly correspond to the maximum size of lock, covered in IS 2209. All the four edges of the door shutter shall be square. The shutter shall be free from twist or warp in its plane and of required size etc. complete as directed. Rate shall include for providing 40 x 5 mm flat iron hold fast 40 cm long including fixing to frame with 10 mm diameter bolts, nuts and wooden plugs and embeddings in cement concrete block 1:3:6 mix (1 cement : 3 coarse sand: 6 graded stone aggregate 20 mm nominal size)				
	32mm thick Fully flush shutter with commercial ply on both sides finished with 1.5 mm thick decorative shade laminate including providing an opening with teakwood lipping for fixing the air transfer grill or louver as per the required size. Rate shall include necessary approved hardwares and louvers as shown in the drawing / as directed. The rate shall include supply of all ironmongers from all doors from Yale/Doorset/Dorma makes.				
	Singleleaf Door 1000 x 2180 mm D6	NOS	6		
5	INTERNAL PAINTING				
	Providing and applying Two or More coats for Internal wall painting with Plastic emulsion paint over two coats of Birla wall care putty of approved brand, colour and quality to give an even shade including preparation of surface, scaffolding, labour, necessary tools & tackles etc., complete at all heights as directed by Engineer-In-Charge.	SQM	188.92		
6	Fixing available Aluminium Glass windows (approximately 5feet x 5feet) available with the Institute, by making necessary adjustments and providing main fixtures as directed by the Engineer incharge.	Nos	2		
TOTAL					