



Indian Institute of Information Technology, Sri City, Chittoor
(An Institute of National Importance under an Act of Parliament)


ADDENDUM 1 DATED 29TH March, 2023

Tender No.: IIITS/NIQ/Drain Work/2023/016,Dt.20/03/2023

Name of work: Providing Storm Water disposal drain channel in basement area in Academic Block at Indian Institute of technology Sri City Chittoor, as per standards.

NIQ Page No.7 – Revised Price Bid ANNEXURE'A'

Bidders to submit the Bids as per the revised Price Bid ANNEXURE'A'



Col.T.Umasankar, Retd.

Registrar

PRICE BID: ANNEXURE 'A'

NIT No. : IITS/NIQ/Drain Work/2023/016, Dt. 20.03.2023

Name of the Work : Providing Storm Water disposal drain channel in basement area in Academic Block at Indian Institute of Information Technology Sri City, Chittoor as per Standards

Name of the Bidder: _____

Sl. No	Description	Qty.	Unit	Rate (In Rs.)	Amount (In Rs.)
1	Cutting/Demolishing the Existing concrete, including cost of machinery, labor, load, lifting and disposal of Rubbish as Instructed by Engineer- in-charge.	15	CUM		
2	Earth work excavation by manual over areas for drain construction, including cost of machinery, labor, load, lifting and disposal of excavated earth as Instructed by Engineer - in - charge.	18	CUM		
3	Providing and laying 75 mm thick PCC 1:4:8 in sub base of Drain including materials, Machinery, Labor, load and lift Centering and shuttering charges as per instructed by Engineer - in - charge.	8	CUM		
4	Providing and laying factory made precast concrete solid blocks of 100mm thickness of grade M10 from approved manufacturer with cement mortar 1:4(1 cement:4 coarse sand) including cost of Material, labor, load, shifting charges as per instructed by Engineer - in - charge.	10	CUM		
5	Providing Water proof Plastering for Drain side Walls of Inner side with 15mm thick(cement Plaster 1:5 1 cement : 5 Sand) including cost of Material, labor, load, shifting charges as per instructed by Engineer - in - charge.	10	CUM		

Signature of the tenderer with seal



6	Providing and fixing in position of RCC pre-cast drain cover slab with size 600x600mm of required shape and approved quality including cost of Material, Steel Reinforcement Bars, cutting, Hooking, Bending to Required Shape, Placing in Position and tying the System with soft Draw Annealed Binding wire with 2 strands, labor, load, shifting charges as per instructed by Engineer - in - charge.	75	Sqm		
Total					

Note: Above rates exclusive of applicable GST.

For & On behalf of IIIT Sri City, Chittoor

Authorized Signatory

