

## **ADDENDUM 3 DATED 22/06/ 2023**

**Tender ID: 2023\_IITS\_757469\_2**

**Tender Reference: IITS\_NIT\_010\_2023**

**NIT: Interior works –Supply, installation, testing & commissioning of Kitchen Equipment’s in the new Dining hall Kitchen along with HVAC (Heating, Ventilation, and Air conditioning) works in the Indian Institute of Information Technology Sri City, Chittoor campus as per the Specification.**

**Pre Bid Meeting Date & Time: 21/06/2023 / 11:00 AM**

**Pre Bid Meeting Venue: IIIT Sri City**

**Pre Bid Meeting Minutes: ATTACHED**

**Tender Reference ID:2023\_IITS\_757469\_2**

**MINUTES OF PRE BID MEETING DATED 21/06/2023**

Sl.No	QUERIES	IIIT Sri City Clarifications
1	EMD Payment	Ref. NIT Clause No: 7 -Page No:-3 The Companies which are registered under MSME are exempted from paying EMD amount as per Government order
2	<b>FINANCIAL BID – BOQ ITEM SL.NO. 4:</b> Supply & installation of SS 304 - 4 DOOR VERTICAL CHILLER - TOP COVER MADE OUT OF 18G SS SHEET, UNIT SHALL BE OF FULL SS CONSTRUCTION WITH INTERIOR AND THE EXTERIOR OF 20/22SWG SS. THE INNER WALL WILL BE SUITABLY INSULATED WITH PUF. IT SHOULD HAVE 4 SELF CLOSING DOORS, CONSTRUCTED OF 22 SWG SS ADJUSTABLE WINGS INSIDE. IT SHOULD BE FITTED WITH DIGITAL TEMPERATURE INDICATOR, CONTROL SWITCHES AND INDICATOR LIGHTS. THE EQUIPMENT SHOULD BE ABLE TO MAINTAIN A TEMPERATURE RANGE OF +2°C TO +8°C. THE UNIT SHALL BE PROVIDED WITH A REMOVABLE SS DRIP TRAY BELOW. THE COMPRESSOR UNIT WILL BE BOTTOM MOUNTED AND SHOULD BE OF A REPUTED MAKE FROM KIRLOSKAR. LEGS SHOULD BE MADE OF 38MM Ø X 16 SWG SS PIPE WITH ADJUSTABLE NYLON BULLET FEET Including cost of all materials, transport, lead, lift etc., complete as per the instruction of Engineer-in - charge	No change in Specification is possible. Bidders are requested to quote for the given specification only. Available room size is 3.05 X 2.0 M is sufficient to accommodate 2 Nos. of 1200 mm X 600 mm size vertical chiller.